8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate quantities for constructing Students' Home at Tumkur.

Items of work.	*Per.*	*Quantity.*
Earthwork excavation and filling basement	C. yd.	413
Concrete foundation	C. ft.	3,167
Stone in chunam foundation and basement	"	8,883
Superstructure—burnt brick in mud	"	9,719
Do in chunam	"	3,255
Archwork—brick in chunam	"	84
Burnt stone slabs	S. ft.	2,499
Burnt stone post with 4 holes bored in it for passing wire	"	204
Slab stone pillars nicely dressed all round	Each	43
Slab stone posts for gateway with holes cut for inserting bamboos	Do	4
Cut stone pillars ($6\frac{1}{2}' \times 9'' \times 9''$) with base and capital	Do	2
Do ($6\frac{1}{2} \times 1' \times 1'$).	Do	2
Chunam plastering	Sqr.	256·59
Do pointing	"	10·50
White and color-washing	"	252·94
Cornice work for front and rear windows	Lump sum.	
Do at gable ends	R. ft.	44
Teakwood work with wood oiling	C. ft.	579·07
Roofing with 1st class Mangalore tiles with teak reepers, complete.	Sqr.	92·68
Ridge tile set in mortar	R. ft.	253
Ornamental ridge tiles	Each	38
Zinc sheet for valleys	S. ft.	136
Kadapa slab stone flooring over sand bed with cement pointing	Sqr.	44·27
Ditto with asphalte pointing	"	0·84
Teakwood doors, pannelled	S. ft.	68
Levelling ground	Lump sum.	
Ventilators, glazed	S. ft.	11
Teakwood windows half pannelled and half glazed in four shutters.	"	48
Teakwood finials	Each.	4
Do for porch	"	1
Ornamental eaveboard all around	R. ft.	442
Barge board for porch including painting	Each.	1
Painting doors and windows	Sqr.	36·86
Teakwood doors, battenned	S. ft.	825
Do windows	"	288
Do do with iron bars	"	268
Shelves in walls with battenned shutters, locks, etc. for the lower half.	"	144
Teakwood planks for shelves	R. ft.	189
Concrete flooring including plastering for dining rooms	C. ft.	202
Twisted galvanized steel wire $\frac{1}{8}$" dia.	"	1·23
Corner posts for wire fencing	Each.	2
Constructing V drains	R. ft.	80
Bamboos for gateway	"	72
Coping with brick in chunam	"	49
Tarring	Sqr.	1·50
Well works—		
Earthwork excavation	C. yds.	127
Burnt stone sheiving with jelly	"	88
Burnt stone slabs 6"	S. ft.	247
Burnt brick in chunam including plastering	C. ft.	95
Iron rail on top of post with pulley etc., complete, including fixing.	Lump sum.	
Bailing water	do	
Clearing site and levelling ground	do	

C. MADAVA RAO, *Offg. Executive Engineer.*

HASSAN DIVISION.

Abstract dated 28th October 1904.

"Invites the attention of the public to the detail advertisement published in the *Mysore Gazette* No. 43, dated 3rd November 1904, calling for tenders for constructing a bridge of 4 arches of 20′ span in 7—16 of Frazerpet-Ramnathpur road."

C. A. MAHADEVA SASTRI *Executive Engineer.*